



1 SECOND FLOOR PLAN  
1/8" = 1'-0"

### SCOPE OF WORK

1. REMOVE EXISTING WORKSTATION AND FURNITURE FROM TECHNICAL SERVICES AREA AND REARRANGE
2. PATCH WALLS AND PREPARE AREA FOR NEW CONSTRUCTION
3. REMOVE EXISTING CEILING GRID AND TILE AT NEW WALL LOCATIONS
4. CONSTRUCT OFFICE 200 WALLS, NEW HOLLOW METAL DOOR FRAME
5. PAINT NEW DOOR FRAME AND WALLS
6. RELOCATE DOOR 225.A FROM OFFICE 225 TO NEW OFFICE 200, WORK DOOR HARDWARE AS REQUIRED
7. REWORK SPRINKLER SYSTEM, LIGHTING (PROVIDE NEW LIGHT SWITCH FOR OFFICE AND CORRIDOR LIGHT FIXTURE), HVAC DIFFUSERS, AND SYSTEMS FOR NEW OFFICE LOCATION
8. REWORK CEILING GRID AND REINSTALL EXISTING CEILING TILE
9. RELOCATE FURNITURE FROM OFFICE 226 INTO NEW OFFICE 200
10. PATCH WALLS AND PREPARE ROOM FOR NEW FURNITURE
11. RELOCATE FURNITURE FROM OFFICE 225 INTO OFFICE 226

# DUBUQUE CARNEGIE-STOUT PUBLIC LIBRARY STAFF AREA REWORK FOR WHISPER ROOM 9.9.2018